

Sl. No.	Item grouped under sub-Heads and Sub-Works of the Estimate
1	Removing B.S. slab of Drain and stacking.
2	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled breaking of clods and neatly dressed as per specifications.
3	Dismantling of existing structures Rubble Stone masonry in cement mortar like culverts, bridges, retaining walls and structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding when necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material all lifts.
4	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and side pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking and complete as per specifications.
5	Providing sand cement bed with 10% cement with all leads for all materials and lift of 1.5 m. machine mixed, laid in layers of 15cms. thick and well compacted for foundation, including curing cost of materials labour and HOM complete as per specifications.
6	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180kgs, with 40mm and downsize graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, concrete in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour and HOM of machinery, curing complete as per specifications.
7	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of ash chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.
8	Construction of size stone masonry with available stones in CM 1: 6
9	Providing and laying in position plain cement concrete of mix M15 with cement @ 240kgs, with 20mm and downsize graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459cum, machine mixed, concrete in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour and HOM of machinery, curing complete as per specifications.
10	Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20mm deep raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.
11	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing complete.
12	Refixing stone slabs of drains and pointing in C.M (1:3).
13	Providing and fixing precast using 20mm and downsize graded coarse aggregate stone using clean leveled approved including and conveyance of all materials, all lead and lift labour charges of machinery etc., complete of 10mm thick directed by engineer incharge CC 1:1.5:3 (inclusive cost of steel and fabrication charges) approved quotation rate.
a	23cms thickness Slab
14	Conveying the excavated earth slit debris and over burden earth etc., to a lead of 10 to 15 kms distance by using vehicle this include the cost of loading and unloading etc., complete.

Certificate

- 1 Certified that the contractor has done the work Satisfactory and found Correct
- 2 Certified that the Contractor has removed all the debris from site.
- 3 Certified that there is no due from the contractor.
- 4 Certified that the contractor making own arrangements for men and materials

[Signature]

[Signature]
 Asst. Executive Engineer
 Yeshwanthpura Sub-Division
 Bruhat Bangalore Mahanagara Palike